Frederick Douglass Greater Rochester International Airport

Request for Bid
Gas-Powered Shuttle Bus, 14-Passenger Capacity Plus Driver

Addendum 1

Release Date: October 13, 2026
Response Deadline: October 30, 2026

MAPCO Auto Parks, As Agent for Monroe County Airport Authority
488 White Spruce Blvd.
Rochester, NY 14623

ADDENDUM ACKNOWLEDGEMENT

Addendum 1 of ____

Changes or revisions to this Solicitation will be made by an official written addendum issued by the MAPCO Auto Parks Ltd. Vendor should acknowledge receipt of all addendum(s) issued with this Solicitation by completing the Addendum Acknowledgment Form included herewith. Failure to acknowledge addendums may result in bid disqualification. **The addendum acknowledgement should be submitted with the bid.**

By my signature below I accept that I have reviewed and acknowledge any addendums that have been issued for this BID.

Please complete the following information:

BIDDER/OFFEROR (Company Name) _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

E-Mail _____

This Signature page must be signed with an original handwritten signature executed in ink and returned with your proposal for your proposal to be considered!

Original Signature _____

Print Name/Title _____

Date _____

An Addendum has been issued to answer the questions listed below.

1. Is a 32” manually operated door acceptable in lieu of a 42” door.
   Denied, 32” door size is too small for passengers carrying luggage, 40” or 42” is allowed.

2. Listing of exceptions/considerations:

   - Only the front portion of the cage is welded. The remaining parts of the cage are assembled using rivets, huck bolts, and structural glue

     All acceptable

   - 32” Manual Door Available, 43” Door would be Electric
     Door must be manual and at least 40”.

   - Front & rear caps are fiberglass
     Acceptable

   - The roof & sides are aluminum. (10 year/ 100,000 Mile Warranty)
     Acceptable but preferred Stainless Steel

   - A 42,000 BTU floor mounted heater and a 20,500 BTU floor mounted heater (62,500 BTU total)
     Both are not acceptable 65,000 BTU Heater for Rear of Bus is mandatory.
     12,000 BTU mandatory for <u>REAR mount</u> unit of Driver’s seat*
     **Please note that this has been changed from the original Bid Spec*

   - Prewire only for the 2-way radio. Dealer to supply and install the remaining components?
     Agreed dealer should supply/install. Wires must be pulled to center dash

   - Interior light package is: 4 LED under seats lights (4’’Wx2.74’’H) 2 stepwell LED lights (3.7’’Wx2.2’’H)
     Agree to both

   - Track seating is not available
     Freedman 17.5” Single ARAC Seats requested in bid

   - Floor cove moldings are not available
     Add spec sheet in submission for alternative option

- They require 18” long lights that is door activated on separate switches and meet ADA requirements = Exception: Requirement appears to prescribe a specific lighting configuration rather than an ADA-mandated performance standard. MicroBird provides LED entry and interior lighting meeting applicable ADA illumination requirements for doorways, steps, and boarding/alighting areas
  This is found to be *Acceptable*

3. Verification of Dealer’s Responsibility and/or Installation:
   - Spare tire / Dealer installed
     Not installed but provided with purchase

   - Delete driver’s armrest / Dealer’s responsibility
     Yes

   - Rustproof inside of doors and panels as well as under carpet/mat. / Dealer installed
     Yes

   - Replacement booster pump for heater system / Dealer installed
     Not installed but provided with purchase

   - Stainless steel wheel inserts / Dealer installed
     Not installed but provided with purchase

   - Rear bumper and brackets / Dealer installed
     Not installed but provided with purchase

   - Set replacement door glass / Dealer’s responsibility
     Not installed but provided with purchase

   - Replacement driver seat / Dealer installed
     Not installed but provided with purchase

   - Transport by truck / Dealer’s responsibility
     Yes, delivered to Monroe County Fleet Center

   - Manual Door Parts Kit
     Provided with purchase

Bus must be transported by truck or trailer to Monroe County Fleet Center, 145 Paul Road, Rochester, NY 14624

All spare parts that are provided with purchase should be placed inside the bus when delivered. Not acceptable to deliver afterwards.